BRUHAT BANGALURU MAHANAGARA PALIKE

SCHEDULE - B

NAME OF THE WORK: Special Repair to School building and Gymnasium Building and with Gym Equipments at Siddarta Nagar in ward no 16, Providing Play Equipments (out Door Gym) in Jalahalli Govt School in ward no 16 and Providing Play Equipments (out Door Gym) in JP Park Inside in ward no 17.

Sl. No.	Description	Unit	Qty	Rates in	
				Figures	words
81	SUPPLYING AND FIXING OF CHEST PRESS DOUBLE – OF SAFE AREA : 4 MTR X 2.5 MTR, OF CENTRE PIPE : 100 NB GI B-class Pipe, SEAT FRAME : 32 NB GI B-CLASS Pipe, HNDLE FRAME : 32 NB & 15 NB GI B-CLASS Pipe, Handle cover : TPEE injection moulded, SEAT REST : LLDP Plastic, PIPE CAP : Nylon 66 injection moulded, BEARING HOUSING AND PIN : Seamless Pipe & Round Bar, BEARINGS : PERMANENT SEALED OF REPUTED MAKE (FAG/SKF), NUT BOLTS CAP : Nylon 66 injection moulded, NUT BOLTS : HIGH TENSILE STEEL, GALVANISED NUT BOLTS, POWDER COAT : DONE BY PURE POLYURETANE POWDER WITH 70 – 80 MICRON THICKNESS AS PER ENGINEER INCHARGE OF THE WORK.	No.	4.00	190740.00	Rupees One Lakh Ninety Thousand Seven Hundred Forty Only
82	SUPPLYING AND FIXING OF FUN ROVER, SAFE AREA : 2.5 MTR X 1.5 MTR., MAIN FRAME : 80 NB GI B-class Pipe, SEAT FRAME : 80 NB GI B-CLASS Pipe, HANDLE FRAME : 32 NB GI B-CLASS Pipe, SEAT : LLDP Plastic, PIPE CAP : Nylon 66 injection moulded, BEARING CAP : Nylon 66 injection moulded, BEARING HOUSING AND PIN : Seamless Pipe & Round Bar, NUT BOLT CAP : Nylon 66 injection moulded, BEARINGS : PERMANRNT SEALED OF REPUTED MAKE (FAG/SKF), NUT BOLTS : HIGH TENSILE STEEL, GALVANISED NUT BOLTS, POWDER COAT : DONE BY PURE POLYURETANE POWDER WITH 70 – 80 MICRON THICKNESS AS PER ENGINEER INCHARGE OF THE WORK.	No.	4.00	66759.00	Rupees Sixty Six Thousand Seven Hundred Fifty Nine Only
83	SUPPLYING AND FIXING OF FUN RIDER, SAFE AREA: 2.5 MTR X 1.5 MTR., MAIN FRAME: 80 NB GI B-class Pipe, SEAT FRAME: 80 NB GI B-CLASS Pipe, HANDLE FRAME: 32 NB GI B-CLASS Pipe, SEAT: LLDP Plastic, PIPE CAP: Nylon 66 injection moulded, BEARING CAP: Nylon 66 injection moulded, BEARING HOUSHING AND PIN: Seamless Pipe & Round Bar, NUT BOLTS CAP: Nylon 66 injection moulded, BEARINGS: PERMANENT SEALED OF REPUTED MAKE (FAG/SKF), NUT BOLTS: HIGH TENSILE STEEL, GALVANISED NUT BOLTS, POWDER COAT: DONE BY PURE POLYURETANE POWDER WITH 70 - 80 MICRON THICKNESS AS PER ENGINEER INCHARGE OF THE WORK.	No.	4.00	166897.00	Rupees One Lakh Sixty Six Thousand Eight Hundred Ninety Seven Only
84	SUPPLYING AND FIXING OF STEP TRAINER OF SAFE AREA : 3 MTR X 1.5 MTR, MAIN FRAME : 100 NB GI B-class Pipe, BOTTOM FRAME : 40 NB GI B-CLASS Pipe, HANDLE FRAME : 32 NB & 15 NB GI B-CLASS Pipe, Handle cover : TPEE injection moulded, FOOT REST : LLDP Plastic, PIPE CAP : Nylon 66 injection moulded, BEARNING CAP : Nylon 66 injection moulded BEARING HOUSING AND PIN : Seamless Pipe & Round Bar, NUT BOLTS CAP : Nylon 66 injection moulded, BEARINGS : PERMANENT SEALED OF REPUTED MAKE (FAG/SKF), NUT BOLTS : HIGH TENSILE STEEL, GALVANISED NUT BOLTS, POWDER COAT : DONE BY PURE POLYURETANE POWDER WITH 70 – 80	No.	4.00	200277.00	Rupees Two Lakh Two Hundred Seventy Seven Only
85	SUPPLYING AND FIXING OF ROLLING BARREL DOUBLE OF SAFE AREA : 2.8 MTR X 1.5 MTR, CENTRE PIPE : 100 NB GI B-CLASS, SEAT FRAME : 32 NB GI B-CLASS Pipe, BACK REST : LLDP Plastic, SEAT REST : LLDP Plastic, FOOT REST : LLDP Plastic, PIPE CAP : Nylon 66 injection moulded, BEARING CAP : Nylon 66 injection moulded, BEARING HOUSING AND PIN : Seamless Pipe & Round Bar, BEARING : PERMANENT SEALED OF REPUTED MAKE (FAG/SKF), STOPER : PU ROD, NUT BOLTS CAP : Nylon 66 injection moulded, NUT BOULTS : HIGH TENSILE STEEL, GALBANISED NUT BOLTS, POWDER COAT : DONE BY PURE POLYURETANE POWDER WITH 70 – 80 MICRON THICKNESS AS PER ENGINEER IN CHARGE OF THE WORK.	No.	4.00	156406.04	Rupees One Lakh Fifty Six Thousand Four Hundred Six and Four Paise Only
86	Providing and erecting direction and place identification retro- reflectorised sign as per IRC :67-2012 made of high intensity grade sheeting vide clause 800.1.3, fixed over aluminium sheeting, 2 mm thick with area exceeding 0.9 sqm supported on a mild steel angle iron post 75 mm x 75 mm x 6 mm, 2 Nos. firmly fixed to the ground by means of properly designed foundation with M-15 grade cement concrete45 cm x 45 cm x 60 cm, 60 cm below ground level as per approved drawing complete as per specifications. MORTH Specification No.801Using Type IV sheeting	Sqm	2.00	8297.00	Rupees Eight Thousand Two Hundred Ninety Seven Only

For K. DAMODAR & CO.

Signature of Contractor
Managing Partner

Executive Engineer
Project Division, R.R.Nagara Zone
Bruhat Bangalore Mahanagara Palike